

**NORTH EASTERN REGIONAL INSTITUTE OF
WATER AND LAND MANAGEMENT (NERIWALM)**
An Institute under the Ministry of Water Resources, River Development
& Ganga Rejuvenation, Govt. of India
(Registered under the Societies Registration Act, 1860)

NRWM/CONSTN/3/2016-17/ 4780

Dated 06.03.2018

SHORT NOTICE INVITING TENDER


Sealed tenders are invited by the Director, NERIWALM, Tezpur from appropriate government registered contractors / firms having experience in similar nature of work as given below. The last date for submission of filled in tender by "REGISTERED POST" or by dropping in the TENDER BOX kept in the lounge of Administrative Building (superscribing the name of the work on the top of the envelope) is **15.03.2018 upto 5.00 PM** and will be opened at **1500 hrs of 16.03.2018** in the conference room of the institute in presence of the tenderer or their authorized representatives, if any. In the event of **15.03.2018** being declared a holiday, the tender will be opened on the next working day at the same time and place. Interested bidders may collect the detailed tender documents along with terms and conditions from the office during all working days upto **1700 hrs of 13.03.2018** after depositing **Rs 100.00 (Rupees one hundred)** only in cash to the Accounts Section of the institute against each group, which is non-refundable. The tenders alongwith terms and condition may be viewed and downloaded from the institute's website. www.neriwalm.gov.in.

Sl. No	Name of work	Estimated amount	Time of completion	Earnest Money
1.	Jungle clearance, surface dressing and providing fencing (DG side) and support of creepers (GH side) behind the Assam Type of NERIWALM Campus.	Rs 1,15,850.00	20 (twenty) days	Rs 2,320.00
2.	Providing structural staging for water reservoir of Assam Type GH of NERIWALM.	Rs 1,00,650.00	20 (twenty) days	2,015.00

Deputy Director
06/03/18
(A K Sharma)
Deputy Director (Admin)

Copy to;

1. The Stenographer attached in the Director's Office for information of Director.
2. The Administrative Officer, LGBRIMH, Tezpur for favour of kind information. He is requested to display the tender notice on the notice board of his office for wide circulation.
3. The Executive Engineer, CPWD, Rubber Bagan, Tezpur for favour of kind information. He is requested to display the tender notice on the notice board of his office for wide circulation.
4. The Executive Engineer, PWD, Tezpur Building Division, Tezpur for favour of kind information. He is requested to display the tender notice on the notice board of his office for wide circulation.
5. The Garrison Engineer, MES, Solmara, Tezpur for favour of kind information. He is requested to display the tender notice on the notice board of his office for wide circulation.
6. The Executive Engineer (civil), CPWD, Rubber Bagan, Tezpur - 1 for information. He is requested to display the tender notice on the notice board of his office for wide circulation.
7. The Accounts Officer, NERIWALM, Tezpur for information & necessary action.
8. The Asstt. Engineer (C) & O.C., Central Stores, NERIWALM, Tezpur for information and necessary action.
9. The Junior Engineer (C) & Store Keeper, Central Stores, NERIWALM, Tezpur for information and necessary action.
10. The Notice Board, NERIWALM, Tezpur for wide circulation & website of NERIWALM www.neriwalm.gov.in.
11. Concerned file for record.




**NORTH EASTERN REGIONAL INSTITUTE OF
WATER AND LAND MANAGEMENT (NERIWALM)**


An Institute under the Ministry of Water Resources, River Development
& Ganga Rejuvenation, Govt. of India

(Registered under the Societies Registration Act, 1860)

TERMS & CONDITIONS

1. The tender should be accompanied with Earnest Money indicated above against each item separately in the form of Demand Draft/Banker's Cheque drawn in favour of Director, NERIWALM, Dolabari, Tezpur without which the tender will be summarily rejected.
2. Self attested Uptodate Contractor's Registration Certificate of appropriate class, Labour Licence, Income Tax Clearance Certificate, PAN Card, GST Registration and Experience Certificate, etc should be submitted alongwith the tender papers.
3. The rates should be legibly written both in figure and in words. Any correction should be authenticated with proper initial.
4. No request for change of rate will be entertained after opening of the tenders.
5. For items such as air conditioners, necessary brochures, write ups and warranty card with servicing details during warranty period should be submitted after completion of the work.
6. 90% payment will be released after completion of the work and the remaining 10% will be retained as Security Deposit for a period of 01 (one) year.
7. As the work is urgent in nature, the work should be completed within the stipulated time. No further extension of time will be granted unless a very strong and satisfactory reason is given.
8. The Contractor should provide necessary risk to the labours from any type of accident that may arise at the work site or within the campus.
9. The materials to be used by the contractor should be got approved from the authority before using the same for the work.
10. Any other clause not covered above, the contractor will be liable to abide by the direction/instruction of the Director, NERIWALM in the interest of the Institute.
11. The Director, NERIWALM reserves the right to accept/reject any or all tenders without assigning any reason thereof and the is no binding on the Director to accept the lowest rate.



(A K Sharma)
Deputy Director (Admin)



Name of the work:-Jungle cleaning, surface dressing and providing Fencing(DG side) and creepers support (Guest house side) behind the Assam type guest house of NERIVALM .

Specification, Bill of Quantities (Rate & Amount to be quoted by the bidder)

SI No	Description of the items	Unit	Qty	Rate (Rs)(Both in figure&words)	Amount(Rs)
1	Jungle clearance including uprooting of vegetation, grass, brush-wood, sapling and trees not exceeding 300 mm girth and disposal of the same outside the periphery and lift upto 1500 mm	Sqm	614.00		
2	Surface dressing of ground including removing vegetation and/ or undulation of ground not exceeding 150 mm deep and disposal of rubbish outside the periphery and lift up to 1800 mm in all kinds of soil	Sqm	614.00		
3	Supplying, fitting and fixing M.S angle, M.S flat, M.S bolts and nuts including painting with red lead paint one coat completely as directed				
	(a) M.S angle/pipe	Qtl	5.02		
	(b) Nut & bolt	Qtl	0.05		
4	Painting one coat (excluding priming coat) on previously painted steel and metal surface with enamel paint of approved brand and manufacture (Asian/Berger/ICI/J&N/Nerolac) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter				
	(ii) Surface upto 100 mm in width or girth				
	(a) General purpose (Asian paint/Berger paint/ICI paint/J & N paint/ Nerolac paint)				
5	(a) M.S angles(ISA-80X80X6 in mm)	Sqm	30.27		
	Earth work in excavation for foundation trenches of walls, retaining wall, footing of column, steps, septic tank, etc including refilling(return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified				
	(A) Upto a depth of 2.00 m below the existing GL				
	(i) In ordinary soil	Cum	4.00		
6	Providing plain/RCC works with cement, coarse sand and 20 mm down graded stone aggregates including dewatering if necessary, and curing complete but excluding cost of form work and reinforcement for RC C works(form work and reinforcement will be measured and paid separately)				
	(i) Using mixture machine				
	(A) In substructure level upto plinth level				
	(a) M15 grade of concrete(1:2:4)	Cum	2.03		



SI No	Description of the items	Unit	Qty	Rate (Rs)(Both in figure&words)	Amount(Rs)
7	Supplying, fitting and fixing chain link fencing of 10 S.W.G, G.I wire 50 mmx 50 mm mesh fitted to M.S angle iron post at 2000 mm apart of specification detailed below including supplying, fitting and fixing hooks, eye bolts with nuts, staples and bolts including three horizontal lines of G.I wire 10 S.W.G at top, middle and bottom and with one vertical line to each fencing tight and erect complete, including one coat of primer painting to M.S angle iron post in P.C.C base etc. with the following. (a) Corner and end posts with M.S angle of size 50mmx50mmx5mm and length not less than 1800 mm only duly stotted and bottom torqued with two numbers as stay posts. (b) Intermediate posts with M.S angle of size 40 mmx 40 mmx5 mm and length not less than 1800 mm only slotte and bottom torqued and splayed © Stay posts with M.S angle of size 35mm x 35mmx5mm and not less than 1800 mm duly slotted and bottom torqued and splayed. All M.S angle iron posts are to be fitted to P.C.C base embeded not less than 600 mm(P.C.C work shall be measured and paid separately)	Sqm	67.50		
8	Dismantling steel work in single sections(R S Joists,channel, angles, tees and flats etc) including dismembering and stacking the materials as directed by the Department for all levels)	Kg	502.00		
9	Demolishing plain cement concrete including disposal of debris as directed for all levels (b) Prop (1:3:6) or rich mix	Cum	1.06		
NOTE: ANY MATERIAL ISSUED BY NERIWALM, THE VALUE OF THE MATERIAL WILL BE DEDUCTED FROM THE BILL VALUE OF THE WORK AS PER BASIC RATE OF APWD (2013-14)				Total(Rs):	

Signature of the party with seal :

Name and address of the party:

Cobnact No: