


Phones: 03712 - 268107/268077
Fax: +91 (03712) 268007
Website: neriwalm.gov.in



Dolabari
P.O. Kaliabhomora
Tezpur - 784 027
Assam (India)



NORTH EASTERN REGIONAL INSTITUTE OF WATER AND LAND MANAGEMENT (NERIWALM)

An Institute under the Ministry of Jal Shakti, Department of Water Resources,
River Development & Ganga Rejuvenation, Govt. of India
(Registered under the Societies Registration Act, 1860)

NO. NRWM/WS/Water Treatment/3/PT-I/2020-21

9872

Date: 14/10/2020

SHORT NOTICE INVITING TENDER

The Director, NERIWALM, Dolabari, Tezpur -784027 (Assam) invites sealed Tender from appropriate registered Firms/Contractor's having valid documents for executing the following work of NERIWALM in the NERIWALM, Campus Dolabari, Tezpur (Assam)


Name of the work : (i) Providing roof covering and vertical cladding above and around the water ATM of NERIWALM, (ii) Providing granite finish to the podium of the statue of Mahatma Gandhi with roof covering above the statue including the earth filling around the podium of NERIWALM Campus. The detail tender papers may be viewed and downloaded from NERIWALM's website www.neriwalm.gov.in.

Dishamur 14/10/2020
Deputy Director(Admin)
NERIWALM

Phones: 03712 - 268107/268077

Fax: +91 (03712) 268007

Website: neriwalm.gov.in



Dolabari

P.O. Kaliabhomora

Tezpur - 784 027

Assam (India)



NORTH EASTERN REGIONAL INSTITUTE OF WATER AND LAND MANAGEMENT (NERIWALM)

An Institute under the Ministry of Jal Shakti, Department of Water Resources
River Development & Ganga Rejuvenation, Govt. of India
(Registered under the Societies Registration Act, 1860)



NO. NRW/WS/Water Treatment/3/PT-I/2020-21/ 9879.

Date: 14/10/2020

SHORT NOTICE INVITING TENDER

The Director, NERIWALM, Dolabari, Tezpur -784027 (Assam) invites sealed Tender from appropriate registered Firms/Contractor's having valid documents for executing the following work of NERIWALM in the NERIWALM, Campus Dolabari, Tezpur. The tender should be submitted by REGISTERED POST or by dropping in the TENDER BOX kept in administrative Building addressed to the Director, NERIWALM, Dolabari, PO-Kliabhomora, Tezpur-784027 (Assam). The tender paper may be viewed and downloaded from NERIWALM's website www.neriwalm.gov.in. The name of the work should be clearly written on the cover of the envelope. The tender will be opened on the conference room of NERIWALM on the date and time mentioned below in the presence of the bidders of their representative if any. In the event of the day being declared holiday, the tender will be opened on the next working day at the same time and place.

The details are given below:-

Sl no	Name of the Job	Estimated amount (RS)	Time of completion	Earnest money deposit	Last date of receipt tender	Date of opening tender
01	Providing roof covering and vertical cladding above and around the water ATM of NERIWALM (Group-I)	99,600.00	30(Thirty) days from the date of issue of formal work order	2% of the quoted amount	10/11/2020 (5.00PM)	11/11/2020 (5.00PM)
02	Providing granite finish to the podium of the statue of Mahatma Gandhi with roof covering above the statue including the earth filling around the podium of NERIWALM Campus (Group-II)	1,12,154.00	40(Forty) from the date issue of formal work order	2% of the quoted amount	10/11/2020 (5.00PM)	11/11/2020 (5.00PM)

Deputy Director(Admin)

उप निदेशक (प्रशासन)

Deputy Director (Administration)

पूर्वोत्तर क्षेत्रीय जल तथा भूमि प्रबंधन संस्थान, तेजपुर
North Eastern Regional Institute of Water and
Land Management, Tezpur

Copy for information & necessary action to:

1. PS to Director for Director's kind information
2. Chief Vigilance Officer, NERIWALM.
3. Assistant Director (Civil), NERIWALM
4. Accounts Officer, NERIWALM
5. Assistant Engineer (Civil)
- ✓ 6. NERIWALM WEBSITE: www.neriwalm.gov.in & CPP portal for publishing.
7. File No: NRW/CONST/231/PT-III/2018-19

TENDER DOCUMENT



SHORT NOTICE INVITING TENDER FOR THE FOLLOWING WORKS:

- Name of the work:** (I) Providing roof covering and vertical cladding above and around the water ATM of NERIWALM (Group-I)
(II) Providing granite finish to the podium of the statue of Mahatma Gandhi with roof covering above the statue including the earth filling around the podium of NERIWALM (Group-II)

of



NORTH EASTERN REGIONAL INSTITUTE OF WATER AND LAND MANAGEMENT

Department of Water Resources, River Development & Ganga Rejuvenation,
Ministry of Jal Shakati, Govt. of India

(Registered under the Societies Registration Act, 1860)

Dolabari, P.O Kaliabhomora

Tezpur-784027, Assam (India)

Website: www.neriwalm.gov.in

Phones: 03712-268107/268007

Fax: +91(03712)268007

NO. NRW/WS/Water Treatment/3/PT-I/2020-21/

Date: 14/10/2020

(Page 1 of 8)

14/10/2020

TECHNICAL DETAILS



1) Name of the work/Supply:

2) Name of the Tendering Party:

3) Name of the Proprietor of the Party/Firm/Company /Agency:

4) Full Address of the Party/Firm/Company/Agency :

5) Telephone/Mobile No:

6) E-mail Address:

7) PAN No:

8) GST Registration No:

9) Labour Licence No:

a) Name of the Labour Licencing Authority

b) Designation:

c) Name of the licencing Authority, with designation, Address:

10) Registration No of the Contractor/Firm :

b) Name of the Registration Authority with designation, address:

Signature of the bidder:

Name (IN BLOCK LETTERS):

Date:.....Place:.....

14/10/2024



Eligibility Criteria & Terms and Conditions:

01. The Bidder should not have been barred/ black listed by any PSU/Govt. Deptt. In dealing business with them (Please submit undertaking).
- 02 Self-attested up-to-date Contractor's Registration Certificate, Labour License, PAN Card, GST Registration, Experience Certificate (copy to be furnished) should be submitted along with tender documents. Make and quality of the materials to be used as mentioned in the nomenclature of the B.O.Q.
- 03 The rates should be legibly written both in figure and in words. Any correction should be properly authenticated with proper initials. The quoted rates should be inclusive of all charges, including GST, taxes etc.
- 04 No request for change of rates will be entertained after opening the tender.
- 05 The selected bidder should have to deposit Performance Security for an amount of 10(ten) percent of the Contract Value in the form of A/C Payee DD/FDR/BG.
- 06 The work should be completed within 45(Forty five) days from the date issue of formal work order . No extension will not be considered except a valid and tenable reason is given and accepted by the Competent Authority.
- 07 The contractor should provide necessary risk to the labours from any type of accident that may arise at the work site or within the campus. Necessary Labour Rules will be applicable on the contractor.
08. Payment will be made as per actual measurement of the work executed.
09. Any other clause not covered under GCC, SCC and above, the contractor will be liable to abide by the directions/instruction of the Director, NERIWALM in the interest of the work.
11. The Tender must accompany Earnest Money Deposit as mentioned in the Tender Notice in the form of **Bank Draft/ Banker's Cheque** from a scheduled Bank payable at Tezpur(Assam) in favour of Director, NERIWALM. Tenders received without EMD/ Inadequate EMD shall be summarily rejected.
12. The earnest money will be to release after deposit of the Performance Security.
13. Any item of work executed as extra item which is beyond the schedule order, the rate will be fixed as per latest APWD SOR with prior approval of Director.
14. The Director, NERIWALM reserves the right to accept/reject any or all tenders without assigning reasons thereof and there is no binding on the Director to accept the lowest rate.

Note: (i) Bidder must provide necessary supporting documents as proof in respect of the eligibility criteria mentioned above (ii) BOQ for quoting the rates attached
(ii) Bidder may quote their rates for any one Group or the whole groups

Signature of the Bidder:.....

Name (IN BLOCK LETTERS):.....

Date:.....**Place:**.....

14/10/2020
Deputy Director (Admin)

उप निदेशक (प्रशासन)

Deputy Director (Administration)

पूर्वोत्तर क्षेत्रीय जल तथा भूमि प्रबंधन संस्थान, तेजपुर
North Eastern Regional Institute of Water and
Land Management, Tezpur



(Group-I)

Name of the work: Providing roof and vertical cladding above & around the WATER ATM of NERIWALM

SPECIFICATION & BILL OF QUANTITIES

SL. NO.	Particulars	Unit	Qty	Rate(In figure & words)	Amount
1	ROOF TRUSS Providing, fitting, hoisting and fixing of roof trusses fabricated out of combination of any two or all of the following sections (i) Square section (ii) Rectangular Hollow section of specification RSH/SHS and (iii) M.S. circular hollow section of Grade 210 including purlins, bottom runners and providing M.S. cleat, M.S. angle base plank, bolts and nuts with red oxide primer including fitting bottom runner and cleat etc. for fixing ceiling joist as per design complete as directed as per specifications.	Qntl	3		
	(b) Using other ISI marked approved brand tube				
2	Supplying fitting and fixing M.S angles , M S falt, M S bolt & nut including painting with red lead paint one coat complete as directed				
	(a) M S angle	Qntl	1.63		
	(b) M S flat	Qntl	1.16		
	© M S bolts and nuts	Qntl	0.05		
3	ROOFING Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) at all levels including fitting and fixing with self drilling, self tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately.) TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement	Sqm	19.5		
	(b) 0.45 mm thick				
4	Providing Pre Painted Galvanized Iron Sheet (PPGI) accessories (Ridges / Valley / Gutter /Flashing) at all levels including fitting and fixing self drilling, self tapping screws complete complete. TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement	Rm	8.50		
	(iii) 0.50 mm thick				
5	Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) at all levels including fitting and fixing with self drilling, self tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately.) TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement	Sqm	24		
	(b) 0.40 mm thick				

Handwritten signature and date:
14/11/2022

SL. NO.	Particulars	Unit	Qty	Rate(In figure & words)	Amount
6	Supplying fitting and fixing wind ties with 40mm x6mm M.S flt iron and necessary 10mm dia G.I hook bolt, G.I flat washer and bitumen washer etc. complete including two coats of painting with red oxide anticorrosive paint	Rm	17.5		
Total(Including GST, charges, taxes etc)					

Page(5 of 8)

(Rupees

) only

Signature of the bidder:

Name (IN BLOCK LETTERS) :

Name of the party /Firm:

Address:

Cont No:

Place:

Date:



Signature
14/10/2020

Deputy Director(Admin)

उप निदेशक (प्रशासन)
Deputy Director (Administration)
पूर्वीक्षर क्षेत्रीय जल तथा भूमि प्रबंधन संस्थान, तेजपुर
North Eastern Regional Institute of Water and
Land Management, Tezpur



Name of the work: Providing Granite finish to the podium of the statue of Mahatma Gandhi with roof covering above the statue and surrounding earth around the podium of NERIWALM Campus

BILL OF QUANTITIES

SI No	Description of the items	Unit	Qty	Rate(In figure & words)	Amount(Rs.)
1	Providing polished granite tiles of approved quality, size and shape and thickness not less than 8 mm , on walls over 15 mm thick, cement mortar bed in prop. 1;3 including cutting where necessary , finished with flush pointing on walls with ordinary cement slurry mixed with approved pigment to match shade of tiles, complete at all levels as specified and directed	Sqm	14.00		
2	ROOF TRUSS Providing, fitting, hoisting and fixing of roof trusses fabricated out of combination of any two or all of the following sections (i) Square section (ii) Rectangular Hollow section of specification RSH/SHS and (iii) M.S. circular hollow section of Grade 210 including purlins, bottom runners and providing M.S. cleat, M.S. angle base plank, bolts and nuts with red oxide primer including fitting bottom runner and cleat etc. for fixing ceiling joist as per design complete as directed as per specifications.				
	b) Using other ISI marked approved brand tube	QNTL	2.8		
3	ROOFING Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) at all levels including fitting and fixing with self drilling, self tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately.) TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement				
	(iii) 0.50 mm thick	Sqm	7.00		
4	Providing Pre Painted Galvanized Iron Sheet (PPGI) accessories (Ridges / Valley / Gutter /Flashing) at all levels including fitting and fixing self drilling, self tapping screws complete complete. TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement				
	(iii) 0.50 mm thick	Rm	6.30		
5	PAINTING WORKS Painting one coat (excluding priming coat) on new steel and metal surface with aluminium paint of approved brand and manufacture (Asian/Berger/ICI/J&N/ Nerolac Paint) and brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter.				
	(i) Surface over 100 mm in width or girth	Sqm	20.00		
(Page 6 of 8)					Continued.....

14/10/2020



SI No	Description of the items	Unit	Qty	Rate(In figure & words)
6	Earth/ sand filling in plinth in layers not more than 150mm thick including necessary carriage, watering, ramming etc. complete as directed and specified including payment of land compensation, forest royalty, sales tax and other duties and taxes as may be necessary.			
	(c) With river sand or silt (predominantly non plastic) by truck carriage including loading and unloading.	cum	40.00	
7	Brick work in cement mortar with 1st class brick including racking out joints and curing complete as directed.			
	(b) In proportion 1:4.	Cum	0.40	
8	Providing and laying plain/reinforced cement concrete works cement, coarse sand & 20mm down graded stone aggregate including dewatering if necessary, and curing complete but excluding cost of form work and reinforcement for reinforced cement concrete work (form work and reinforcement will be measured and paid separately)			
	N) Without using admixture, plasticiser			
	a) M15 grade concrete or Prop. 1:2:4	cum	0.75	
9	10 mm thick Cement plaster in single coat on fair side of brick/concrete walls for interior plastering up to 1st floor level including arises or rounded angles not exceeding 80mm girth and finished even and smooth including curing complete as directed.			
	b) In cement mortar 1:4	SQM	18.00	
10	Supplying, fitting, fixing M.S angle, M.S flat, M.S bolts and nuts including painting with red lead paint with one coat in complete			
	(c) M.S bolts & nuts	Qtl	0.10	
	(b) M.S flats	Qtl	0.40	
11	Supplying fitting and fixing wind ties with 40mm x6mm M.S flat iron and necessary 10mm dia G.I hook bolt, G.I flat washer and bitumen washer etc. complete including two coats of painting with red oxide anticorrosive paint	Rm	8.85	
(Page 7 of 8)				Continued

Handwritten signature
14/10/2021

Sl No	Description of the items	Unit	Qty	Rate(In figure & words)	Amount(Rs.)
12	POWER CABLE :Supplying and laying following nos & size Power cable/control PVC/XLPE insulated and PVC sheathed 1.1 KV grade Solid Aluminium conductor up to 10 Sqmm balance stranded conductor, XLPE insulated, cores laid up, PVC tape inner sheathed, Armour(Aluminium for single core upto 70 Sqmmbalance Aluminium strips, Gavanised for cables up to 2x10 Sqmm.3x10 sqmm,4x6 sqmmbalance all galvanised steel strip), extruded PVC Type ST2 sheathed, 650/1100V grade as per IS 7908(Part -1) 1988 armoured U.G cable laid in ground/partially in air(as required for termination over ground including excavation of cable trench up to depth of 75 cm, refilling, protective brick covering, sand cushioning etc complete handling of surplus soil, debris etc. to proper place as specified and directed by the deptt, (Nicco/Havells/RPG/CCI/Polycab/Gloster/ Finolex make equivalent)				
	3 Core A2XFYA2XFY				
	10.00 mm 3 core armoured U.G cable	Mtr	60		
13	(A2) Supplying and laying following nos and size solid Aluminium conductor up to 10 Sqmm balance stranded conductor , XLPE insulated, cores laid up, PVC tape inner sheathed, Armour (Aluminium for single core upto 70 sqmm balance Aluminium strips, Galvanised for cables up to 2x10 Sqmm 3x10 sqmm, 4x6 sqmm balance all galvanised steel strip), extruded PVC tYPE ST2 sheated ,650/1100 V grade as per IS 7908(Part-I) 1988 armoured U.G cable laid in pucca flooring, road crossing, drain crossing as per site requirement and partially in air(as required for termination over ground including excavation of cable trench upto depth of 75 cm,refilling, protective brick soling, sand cushioning etc complete handling of surplus soil, debris etc. to proper place as specified and directed by Deptt(Nicco/Havells/RPG/CCI/Polycab/Gloster/ Finolex make equivalent)				
	10.00 mm 3 core armoured U.G cable in 32 mm dia G	Rm	6		
(Including GST, all the charges, taxes etc) Total(Rs)					

(Rupees.....) only

Signature of the Bidder:

Name (IN BLOCK LETTERS) :

Name of the party/Firm:

Address :

Cont No:

Date :

Place



(Page 8 of 8)


 Deputy Director (Admin)
 Deputy Director (Administration)
 पूर्वोत्तर क्षेत्रीय जल तथा भूमि प्रबंधन संस्थान, तेजपुर
 North Eastern Regional Institute of Water and
 Land Management, Tezpur