

Name of the work : Providing interlocking concrete block pavement and surface drain on the yard in front of the Rain Water Reservoir Tank of NERIWALM

BILL OF QUANTITIES

Sl no	Description	Unit	Qty	Rate	Amount (Rs)
1	Interlocking concrete Block pavement (A) Interlocking pavement Block Providing and laying interlocking concrete block pavement (M40) having thickness 80 mm as per technical specification clause 1504 complete (a) Including Edge block/Edge Restraints	Sqm	90.57		
2	Providing drain with brick work in cement mortar in prop. 1:5 with half brick sides wall and 100 mm thick C.C (1:3:6) base over one brick flat soling including 15 mm thick cement plastering in prop. 1:3 finished with a floating coat of cement slurry as directed with necessary shuttering for sides and earth work in excavation of foundation of foundation trenches and refilling the sides after completion of work etc. as directed (ii) 300 mm wide and average 250 mm deep with bed slope 1 in 150 with initial depth of 100 mm	RM	51.00		
3	Earth /sand filling in plinth in layers not more than 150 mm thick including necessary carriage, watering, ramming etc. complete as directed and specified including payment of land compensation, forest royalty, sales taxes and other duties and taxes as may be necessary © With river sand or silt (predominantly non-plastic) by truck carriage including loading and unloading.	Cum	18.75		
TOTAL :					

Name & Signature of Contractor/Party :

Contact No :

Address :